


THIS PLAN TO BE USED FOR SETTING OUT OF TREE PROTECTION MEASURES ONLY; DO NOT SCALE FROM THIS PLAN UNLESS IT IS PRINTED AT A1. DO NOT **USE UNLESS PRINTED IN** COLOUR







Tree to be removed

Position of fixed Hoarding style fencing

Challice Consulting Ltd. annotation

Tree protection barrier and ground

protection to be erected and installe before machinery or materials are brought onto site, before any demolition or development of land

Tree protection measures should be Implemented following any necessary pre-development tree

Where due to site constraints, construction activity cannot be fully or permanently excluded from all or part of a trees Root Protection Area, appropriate ground protection should be installed.

Barriers and ground protection must not be removed or altered except with prior recommendation by project arboriculturist and where necessary, approval from the Local Planning Authority.

Setting out to be confirmed by project arborlculturist prior to ommencement of other opera

The ground protection detail is to be used where the tree protection barrier needs to be set back so that it will expose unmade ground to construction activity. New. temporary ground protection should be installed as part of the physical tree protection measures prior to starting work on site.

Suitable existing hard surfacing not proposed for re-use as part of the finished design shall be retained as ground protection within root protection areas, where and as long as, it is possible.

Plan to be printed in colour and to scale

Tree Protection Plan

1 Montana Road, Wimbledon, London SW20 8TW

1:100 @ A1 0.05.2019 D.C. TPP-CC/980 AR4005



Challice Consulting Ltd. Holmwood Farm Grange Horsham Road North Holmwood Dorking Sorking
Surrey
RH5 4JR
Tel: 01306 743374
Email: info@challiceconsulting.co.uk
Web: www.challlceconsulting.co.uk

This page is intentionally left blank